



BILL OF QUANTITIES AND UNIT COST AS AWARDED

CONTRACT NUMBER: CW-MP-05-2026
PROJECT : CUBA SADSADAN CIS
CONTRACTOR : A3-BUILDERS AND CONSTRUCTION SUPPLY

DESCRIPTION		QUANTITY	UNIT	UNIT COST	AMOUNT
I.	INTAKE WORKS				
a	Clearing and Grubbing	841.00	sq.m.	29.52	24,826.32
b	Procurement, Delivery & Installation of 3.0" Ø HDPE Pipe SDR 17	882.00	ln.m.	572.55	504,989.10
c	Procurement, Delivery & Installation of 2.0" Ø HDPE Pipe SDR 17	1,150.00	ln.m.	268.18	308,407.00
d	Other Materials and Accessories	1.00	Lot	44,110.50	44,110.50
e	12 mm Ø x 6m RSB	5.00	pcs		
	3"HDPE Pipe tee (Compression)	3.00	pcs		
	2" HDPE Pipe Tee (Compression)	2.00	pcs		
	3" Ø HDPE Ball Valve	2.00	pcs		
	2" Ø HDPE Ball Valve	7.00	pcs		
	3" Ø - 2"Ø HDPE Pipe Reducer	4.00	pcs		
II.	CANAL STRUCTURES				
a	Common Structural Excavation	0.84	cu.m.	672.77	565.13
b	211 kg./sq.cm. Reinforced Concrete	1.07	cu.m.	23,916.26	25,590.40
c	Procurement, Delivery & Installation of 3/8" Ø Cable Wire	30.00	li.m	196.53	5,895.90
d	Procurement, Delivery & Installation of 3.0" Ø HDPE Pipe	18.00	li.m	621.40	11,185.20
e	Other Materials and Accessories	1.00	lot	8,008.88	8,008.88
	16mm' 'Ø x 1.0m RSB (SADDLE)	2.00	ln.m		
	12mm' 'Ø x 0.5m RSB (Cable Guide)	2.00	ln.m		
	16mm Ø x 1.5m RSB (ANCHOR)	3.00	ln.m		
	3/8" Ø CABLE CLIP	10.00	Pc.		
	2"Ø x 0.15m GI pipe (Cable Guide)	2.00	Pc.		
	Tie Wire #10 (Suspender)	1.00	Roll		
III	TERMINAL FACILITIES				
a	Structure Excavation	3.54	Cu.m	432.31	1,530.38
b	Gravel Blanket	0.71	Cu.m	7,657.79	5,437.03
c	211 kg./sq.cm. Reinforced Concrete	5.39	kgs.	27,309.25	147,196.86
d	Other Materials and Accessories	1.00	lot	107,987.25	107,987.25
	I. FROM SUPPLY				
	2 "Ø Pipe	16.20	Ln.m		
	EMT Clamp	24.00	pcs.		
	II. OVERFLOW & DRAIN PIPELINE				
	2.0" Ø X 1.75 m length	6.00	ln.m.		
	2.0" Ø Ball Valve (Drain)	12.00	pcs.		
	2.0"Ø 90° Elbow	6.00	pcs.		
	2.0"Ø X 0.3m (Overflow and Drain)	18.00	pcs.		
	2.0"Ø X 0.15m (Drain)	12.00	pcs.		