

BILL OF QUANTITIES
(Building Construction/Rehabilitation Project)

PROJECT TITLE : REHABILITATION OF COMMONWEALTH HEALTH CENTER WITH INSTALLATION OF SOLAR POWER SYSTEM INCLUDING BATTERY STORAGE
LOCATION : BARANGAY COMMONWEALTH
PROJECT NO. : OCM-CDF(ENGINEERING)-26-BLDG-00057
DURATION : ONE HUNDRED FIFTY (150) CALENDAR DAYS

ITEM CODE	DESCRIPTION	QUANTITY	UNIT	ESTIMATED DIRECT COST	MARK-UP IN %		TOTAL MARK-UP		VAT	TOTAL INDIRECT COST	TOTAL COST	UNIT COST
					OCM	PROFIT	%	VALUE				
PART I	OTHER GENERAL REQUIREMENTS											
B.5	Project Billboard / Sign Board	1.00	each									
B.7(1)	Occupational Safety and Health	5.00	month									
B.9	Mobilization	1.00	unit									
B.9	Demobilization	1.00	unit									
B.20	Temporary Enclosure	30.00	l.m.									
B.24	Scaffolding (Rental)	53.00	sq.m.									
	TOTAL OF PART I											
PART II	CIVIL, SANITARY/PLUMBING, ELECTRICAL AND MECHANICAL WORKS											
PART A	REMOVAL WORKS											
801(2)	Removal of Sanitary / Plumbing Fixtures	47.00	piece									
801(3)	Removal of Concrete / Masonry Structure	8.00	sq.m.									
801(3)	Removal of Doors and Windows	98.00	sq.m.									
801(3)	Removal of Tiles / Floor Topping	529.00	sq.m.									
801(3)	Removal of Ceiling	307.00	sq.m.									
801(3)	Removal of Roofing Sheet including Accessories	323.00	sq.m.									
801(3)	Removal of ACP including Framing and Accessories	33.00	sq.m.									
801(3)	Chipping Works	44.00	sq.m.									
	TOTAL OF PART A											
	EARTHWORKS											
803(1)c	Structure Excavation (Solid Rock)	3.00	cu.m.									
804(1)a	Embankment from Structure Excavation	2.00	cu.m.									
804(4)	Gravel Fill	1.00	cu.m.									
	TOTAL OF PART B											