

Section VIII. Bill of Quantities

Project Identification Number:
Project Name:

Location:

CW-KALINGA-08-2023
UPPER CHICO RIVER IRRIGATION
SYSTEM
Tabuk City, Kalinga

ITEMS OF WORK	QUANTITY	UNIT	AMOUNT
I. CANALIZATION WORKS			
LATERAL D-AGBANNAWAG-TUROD, BULO			
A. Common Excavation (Mechanized)	204.71	cu.m	17,095.90
B. Gravel Blanket	25.67	cu.m	53,889.64
C. Reinforcing Steel Bars	10,348.54	kgs	1,122,932.49
D. 170 kg./sq.cm Reinforced Concrete	120.21	cu.m	934,638.06
E. 211 kg./sq.cm Reinforced Concrete	66.30	cu.m	840,989.58
F. Backfill with Compaction (Mechanized-Haul)	1,435.53	cu.m	395,179.59
II.CANAL STRUCTURE WORKS			
LATERAL D-AGBANNAWAG-TUROD, BULO			
G. Structure Excavation (Mechanized)	11.14	cu.m	1,240.40
H. Gravel Blanket	2.32	cu.m	4,870.43
I. Reinforcing Steel Bars	899.28	kgs	97,581.95
J. 211 kg./sq.cm Reinforced Concrete	15.71	cu.m	199,275.21
K. Rubble Masonry	17.76	cu.m	130,252.63
L. Backfill with Compaction (Mechanized-Haul)	64.10	cu.m	17,645.76
M. Construction Safety and Health	2,788.00	man-day	36,383.40
APPROVED BUDGET FOR THE CONTRACT			3,851,975.04