

BILL OF QUANTITIES
(Building Construction/Rehabilitation Project)

PROJECT TITLE : DRAINAGE SYSTEM AT BIAK NA BATO STREET (FROM DON MANUEL STREET TO N.S. AMORANTO STREET) IN BARANGAY STO. DOMINGO
LOCATION : BARANGAY STO. DOMINGO
PROJECT NO. : OCM-LDRRMF(ENGINEERING)-26-FLOOD-00013
DURATION : ONE HUNDRED TWENTY (120) CALENDAR DAYS

ITEM CODE	DESCRIPTION	QUANTITY	UNIT	ESTIMATED DIRECT COST	MARK-UP IN %		TOTAL MARK-UP		VAT	TOTAL INDIRECT COST	TOTAL COST	UNIT COST
					OCM	PROFIT	%	VALUE				
PART I	OTHER GENERAL REQUIREMENTS											
B.5	Project Billboard / Sign Board	2.00	ea									
B.7(1)	Occupational Safety and Health	4.00	mo									
B.9 (1)	Mobilization	1.00	unit									
B.9 (2)	Demobilization	1.00	unit									
	TOTAL OF PART I											
PART II	EARTHWORKS											
PART A	REMOVAL OF STRUCTURES											
101(3)b3	Removal of Actual Structure/ Obstruction, 0.23m thick, PCCP (Unreinforced)	1,330.00	sq.m.									
101(4)c	Removal of Actual Structural Obstruction, Curb & Gutter	270.00	l.m.									
	TOTAL OF PART II.A.											
PART B	STRUCTURE EXCAVATION											
102(2)	Roadway Excavation	133.00	cu.m.									
103(1)a	Structure Excavation, Hard Rock	1,234.00	cu.m.									
	TOTAL OF PART II.B.											
	TOTAL OF PART II											
PART III	CIVIL WORKS											
PART A	SUB-BASE AND BASE COURSE											
201(1)	Aggregate Base Course	140.00	cu.m.									
	TOTAL OF PART III.A.											
PART B	SURFACE COURSES											
311(1)c2	Portland Cement Concrete Pavement, 0.23m thick, 7 days	1,405.00	sq.m.									
	TOTAL OF PART III.B.											
PART C	DRAINAGE AND SLOPE PROTECTION STRUCTURES											

BILL OF QUANTITIES
(Building Construction/Rehabilitation Project)

PROJECT TITLE : DRAINAGE SYSTEM AT BIAK NA BATO STREET (FROM DON MANUEL STREET TO N.S. AMORANTO STREET) IN BARANGAY STO. DOMINGO
LOCATION : BARANGAY STO. DOMINGO
PROJECT NO. : OCM-LDRRMF(ENGINEERING)-26-FLOOD-00013
DURATION : ONE HUNDRED TWENTY (120) CALENDAR DAYS

500(1)a4	Pipe Culverts, 1070mm dia., RCPC	238.00	I.m.																
500(5)	Tapping Drainage	21.00	set																
502(1)a3-5	Manholes, 1070mm dia., Concrete	21.00	each																
502(1)d	Detention Basin (8m x 8m x 2m)	1.00	set																
502(5)a1	Metal Frame & Gratings, Hot Dipped Galvanized Iron (1.0 m x 1.0 m)	21.00	set																
1716(6)b	Structural Steel Sheet Pile, Furnished (Rental)	23,040.00	kg																
1716(12)	Structural Steel Sheet Pile, Driven	240.00	I.m.																
1716(29)	Structural Steel Sheet Pile, Extracted	240.00	I.m.																
	TOTAL OF PART III.C.																		
PART D	MISCELLANEOUS STRUCTURES																		
600(4)	Curb and Gutter (Cast in Place)	284.00	I.m.																
612(1)	Reflectorized Thermoplastic Pavement Markings White	55.00	sq.m.																
612(2)	Reflectorized Thermoplastic Pavement Markings Yellow	49.00	sq.m.																
625(4)	Steel Barricade (Rental)	24.00	unit																
	TOTAL OF PART III.D.																		
	TOTAL OF PART III																		
	GRAND TOTAL																		