

BILL OF QUANTITIES

PROJECT TITLE : REHABILITATION OF BAGONG SILANGAN SUPER HEALTH CENTER (PHASE 2) WITH INSTALLATION OF SOLAR POWER SYSTEM INCLUDING BATTERY STORAGE AT BRGY. BAGONG SILANGAN

LOCATION : BARANGAY BAGONG SILANGAN

PROJECT NUMBER : OCM-CDF(ENGINEERING)-26-BLDG-00067

DURATION : ONE HUNDRED FIFTY (150) CALENDAR DAYS

ITEM CODE	DESCRIPTION	QUANTITY	UNIT	ESTIMATED DIRECT COST	MARK-UP IN % OCM	PROFIT	TOTAL MARK-UP %	VALUE	VAT	TOTAL INDIRECT COST	TOTAL COST	UNIT COST
PART I OTHER GENERAL REQUIREMENTS												
B.5	Project Billboard/Signboard	1.00	each									
B.7(1)	Occupational Safety and Health Program	5.00	month									
B.9	Mobilization	1.00	unit									
B.9	Demobilization	1.00	unit									
B.20	Temporary Enclosure	64.00	l.m.									
B.24	General Scaffolding (Rental)	243.00	sq.m.									
	TOTAL OF PART I											
PART II CIVIL, PLUMBING/SANITARY, ELECTRICAL AND REMOVAL WORKS												
800(1)	Clearing and Grubbing	256.00	sq.m.									
801	Removal of Sanitary/Plumbing Fixtures	21.00	piece									
801	Removal of Concrete/Masonry Structure	275.00	sq.m.									
801	Removal of Doors and Windows	50.00	sq.m.									
801	Removal of Tiles / Floor Topping	355.00	sq.m.									
801	Removal of Ceiling	240.00	sq.m.									
801	Removal of Grills / Railings / Gate including Accessories	9.00	sq.m.									
801	Chipping Works	355.00	sq.m.									

BILL OF QUANTITIES

PROJECT TITLE :	REHABILITATION OF BAGONG SILANGAN SUPER HEALTH CENTER (PHASE 2) WITH INSTALLATION OF SOLAR POWER SYSTEM INCLUDING BATTERY STORAGE AT BRGY. BAGONG SILANGAN
LOCATION :	BARANGAY BAGONG SILANGAN
PROJECT NUMBER :	OCM-CDF(ENGINEERING)-26-BLDG-00067
DURATION :	ONE HUNDRED FIFTY (150) CALENDAR DAYS

TOTAL OF PART A					
PART B	EARTHWORKS				
803(1)a	Structure Excavation (Solid Rock)	35.00	cu.m.		
804(1)a	Embankment from Structure Excavation	28.00	cu.m.		
804(4)	Gravel Fill	3.00	cu.m.		
1000(1)	Soil Poisoning	54.00	L		
TOTAL OF PART B					
PART C		CIVIL AND STRUCTURAL WORKS			
C.1. Plain and Reinforced Concrete Works					
900(1)c1	Structural Concrete, Class A, 28 days, 3000 psi	9.00	cu.m.		
900(1)c2	Structural Concrete, Class A, 28 days, 4000 psi	8.00	cu.m.		
902(1)a	Reinforcing Steel (Deformed), Grade 40	584.00	kg		
902(1)b	Reinforcing Steel (Deformed), Grade 60	1,007.00	kg		
903(2)	Formworks and Falseworks	102.00	sq.m.		
C.2. Plain and Reinforced Concrete Works					
GENERATOR SET ROOM					
1047(1)	Structural Steel, 50 mm x 50 mm x 2 mm Tubular Bar	87.00	kg		
1047(1)	Structural Steel, 25 mm x 25 mm x 2 mm Angle Bar	47.00	kg		
1047(1)	Structural Steel, 50 mm Ø G.I. Pipe	136.00	kg		
1047(6)	Metal Structure Accessories, Base Plate	1.00	kg		
1047(10)	Metal Structure Accessories, 50 mm x 50 mm x 4.5 mm Wire Mesh	16.00	sq.m.		
1047(4)a1	Metal Structure Accessories, 12 mm Ø x 120 mm Anchor Bolt	16.00	each		
GENERATOR SET ROOM					