

Section VIII. Bill of Quantities

Project Identification Number:
Project Name:
Location:

CW-APAYAO-01-2025
WEST APAYAO ABULUG IS
Pudtol, Apayao

DESCRIPTION		QUANTITY	UNIT	AMOUNT
	CONTRACT WORKS			
	A. TEMPORARY FACILITIES			
	1. Project Billboard	1.00	lot	9,329.47
	B. MOBILIZATION AND DEMOBILIZATION			
	1. Mobilization and Demobilization	1.00	lot	1,052,366.52
	C. CONSTRUCTION SAFETY AND HEALTH PROGRAM			
	1. Construction Safety and Health Program	7,217.00	man-days	93,582.20
	D. DIVERSION WORKS			
	a. 211 kg/sq.cm Concrete	1,025.80	cu.m.	16,510,045.84
	b. RSB			
	b.1. Furnish and Stockpile	71,806.00	kgs.	8,141,364.28
	b.2. Cut, Bend and Install	71,806.00	kgs.	2,242,501.38
	c. Common Excavation (Equipment)	13,677.49	cu.m.	2,699,799.75
	d. Borrow Haul	2,188.27	cu.m.	763,815.64
	e. Rubble Masonry	1,995.37	cu.m.	25,315,398.87
	f. Demolition of Concrete	188.70	cu.m.	104,232.22
	g. 50 mm dia. PVC Pipe (6m)			
	Supply and Delivery	201.00	pcs	351,428.40
	Installation	201.00	pcs	94,433.82
	h. 100 mm dia. PVC Pipe (6m)			
	Supply and Delivery	44.00	pcs	228,120.64
	Installation	44.00	pcs	20,672.08
	i. Cofferdamming	1.00	lot	923,711.97
	j. Sheet Piles			
	Supply and Delivery	3,240.00	ln.m.	39,213,946.80
	Installation	3,240.00	ln.m.	885,006.00
	APPROVED BUDGET FOR THE CONTRACT			98,649,755.88