


BILL OF QUANTITIES AND UNIT COST AS AWARDED


CONTRACT NUMBER: CW-ALSP-04-2024
 PROJECT : ALFONSO LISTA SOLAR PUMP IRRIGATION PROJECT 04
 CONTRACTOR : ASC CONSTRUCTION & CONCRETE PRODUCTS

DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
10. Construction of Perimeter Fence, Stilling Pool, and NIA Logo (3units)				
10.1.) Structure Excavation (Manual)	47.70	cu.m.	1,727.42	82,397.93
10.2.) Structure Backfill (Manual)	8.40	cu.m.	202.07	1,697.39
10.3.) Gravel Blanket	6.00	cu.m.	6,684.83	40,108.98
10.4.) 211 kg./sq.cm Concrete (Class "A") - 3000 Psi	39.75	cu.m.	21,796.16	866,397.36
10.5.) Reinforcing Steel Bar, RSB (All sizes)	3,695.73	kgs	291.43	1,077,046.59
10.6.) Painting Works	71.04	sq.m.	788.92	56,044.88
10.7.) Water Proofing	141.00	sq.m.	438.81	61,872.21
10.8.) Perimeter Fence	3.00	lot	1,695,750.00	5,087,250.00
10.9.) Solar Street Light	18.00	pcs	4,690.00	84,420.00
10.10.) Overhaul Waste Disposal	39.30	cu.m.	254.95	10,019.54
11. Construction of Control Room (3 units)				
11.1.) Structure Excavation (Manual)	30.00	cu.m.	1,727.42	51,822.60
11.2.) Structure Backfill (Manual)	13.59	cu.m.	202.07	2,746.13
11.3.) Gravel Blanket	4.35	cu.m.	6,684.83	29,079.01
11.4.) 211 kg./sq.cm Concrete (Class "A") - 3000 Psi	26.82	cu.m.	21,796.16	584,573.01
11.5.) Reinforcing Steel Bar, RSB (All sizes)	3,950.52	kgs	291.43	1,151,300.04
11.6.) Laying and Plastering of 4" thk. CHB (Both Sides)	132.18	sq.m.	2,596.89	343,256.92
11.7.) Supply, Delivery, & Installation of Door (1500mm x 2100mm)	3.00	set	30,940.00	92,820.00
11.8.) Supply, Delivery, & Installation of Window (1800mm x 1450mm)	3.00	set	35,105.00	105,315.00
11.9.) Water Proofing	58.66	sq.m.	438.81	25,740.59
11.10.) Painting Works	355.38	sq.m.	788.92	280,366.39
11.11.) Overhaul Waste Disposal	16.41	cu.m.	254.95	4,183.73
12. Intake Works				
12.1.) Excavation				
a. Common	85.20	cu.m.	166.60	14,194.32
12.2.) Backfill with Compaction	233.50	cu.m.	297.50	69,466.25
12.3.) Rubble Masonry	412.50	cu.m.	15,115.63	6,235,197.38
12.4.) 211 kg./sq.cm Concrete (Class "A") - 3000 Psi	44.16	cu.m.	21,796.16	962,518.43
12.5.) Reinforcing Steel Bar, RSB (All sizes)	4,973.63	kgs	291.43	1,449,464.99
12.6.) Supply, Delivery, and Installation of Slide Steel Gate w/ CP 12 Type Lifting Mechanism including embedded parts and all accessories (1800mm x 2200mm)	2.00	assy.	910,350.00	1,820,700.00
12.7.) Supply, Delivery, and Installation of Trashrack (including all accessories)	2.00	assy.	511,700.00	1,023,400.00
12.8.) Steel Sheetpile				
12.8.1) Supply and Delivery	210.00	ln.m.	13,387.50	2,811,375.00
12.8.2) Installation	210.00	ln.m.	145.12	30,475.20
13. Construction Health and Safety	1.00	l.s.	256,600.00	256,600.00
TOTAL CONTRACT COST				204,666,607.95

APPROVED :


 BENITO T. ESRIOUE, JR.
 REGIONAL MANAGER A
 NIA-CAR

CONFORME:


 ABRAHAM S. COLLADO
 General Manager
 ASC CONSTRUCTION & CONCRETE PRODUCTS