

BILL OF QUANTITIES AND UNIT COST AS AWARDED

CONTRACT NUMBER: CW-ALSPIP-03-2024
PROJECT : ALFONSO LISTA SOLAR PUMP IRRIGATION PROJECT 03
CONTRACTOR : ASC CONSTRUCTION & CONCRETE PRODUCTS

DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
<i>Construction of 3 Units 50HP PV Submersible Pumping System-Surface Type</i>				
1. Temporary Works, Const. Plant, Mobilization of Construction Equipment & Demobilization Works	1.00	l.s.	1,035,441.60	1,035,441.60
2. Diversion Care of River during Construction and Unwatering Foundation	1.00	l.s.	1,335,000.00	1,335,000.00
3. Supply, Delivery, and Installation of 50HP Submersible Pump				
3.1.) Submersible Pump (50HP) -4.5m ³ /min. @ 24.5m TDH, 380V/440v, 60Hz, 3 Phase				
3.1.1.) Supply and Delivery	3.00	assy.	14,100,000.00	42,300,000.00
3.1.2.) Installation and Testing of Pump	3.00	assy.	829,032.00	2,487,096.00
Total for Submersible Pump				44,787,096.00
4. Supply, Delivery, and Installation of Valves				
4.1.) 200mm Gate Valve				
4.1.1.) Supply and Delivery	3.00	assy.	792,000.00	2,376,000.00
4.1.2.) Installation and Testing of Gate Valve	3.00	assy.	238,800.00	716,400.00
4.2.) 200mm Check Valve				
4.2.1.) Supply and Delivery	3.00	assy.	792,000.00	2,376,000.00
4.2.2.) Installation and Testing of Check Valve	3.00	assy.	238,800.00	716,400.00
Total for Valves				6,184,800.00
5. Supply, Delivery, and Installation of Discharge Pipes				
5.1.) 300mm Ø B.I. Pipe (5mm Thk)				
5.1.1.) Supply and Delivery	600.00	ln.m.	20,100.00	12,060,000.00
5.1.2.) Installation & Testing of Pipe	600.00	ln.m.	5,040.00	3,024,000.00
5.2.) Structure Excavation (Manual)	447.12	cu.m.	1,741.93	778,851.74
5.3.) Structure Backfill (Manual)	280.80	cu.m.	203.77	57,218.62
5.4.) 211 kg/sq.cm. Concrete (Class A) -3000 Psi	224.64	cu.m.	21,979.32	4,937,434.44
5.5.) 1/4" x 6" 100% Virgin Neoprene Pad w/ Durometer Hardness (50) Adhere to the Saddle	113.26	ln.m.	1,170.00	132,514.20
Total for Discharge Pipes				20,990,019.00
6. Supply, Delivery, and Installation of Solar Powered VFD Controller				
6.1.) Supply and Delivery of Solar Powered VFD Controller	3.00	assy.	1,692,000.00	5,076,000.00
6.2.) Installation of VFD Controller	3.00	assy.	318,000.00	954,000.00
6.3.) Wiring & Cabling	1.00	lot	264,000.00	264,000.00
Total for VFD Controller				6,294,000.00
7. Supply, Delivery, & Installation of Solar Panel and its accessories				
7.1.) PV Modules (Solar Panel 700watts)				
7.1.1.) Supply and Delivery	216.00	pcs	43,500.00	9,396,000.00
7.1.2.) Installation	216.00	pcs	2,085.00	450,360.00
7.2.) Inverter				
7.2.1.) Supply and Delivery	6.00	assy.	996,000.00	5,976,000.00
7.2.2.) Installation	6.00	assy.	27,800.00	166,800.00
7.3.) DC Cable from PV String (1 x 35mm ²)				
7.3.1.) Supply and Delivery	300.00	ln.m.	990.00	297,000.00
7.3.2.) Installation	300.00	ln.m.	115.84	34,752.00
7.4.) AC Cable (125mm ²)				
7.4.1.) Supply and Delivery	300.00	ln.m.	3,780.00	1,134,000.00
7.4.2.) Installation	300.00	ln.m.	538.07	161,421.00
7.5.) 1.5" Ø RSC Conduit				
7.5.1.) Supply and Delivery	320.00	ln.m.	2,274.00	727,680.00
7.5.2.) Installation	320.00	ln.m.	336.97	107,830.40
7.6.) 3" Ø RSC Conduit				
7.6.1.) Supply and Delivery	68.00	ln.m.	3,984.00	270,912.00
7.6.2.) Installation	68.00	ln.m.	597.85	40,653.80
7.7.) MC4 Connector				
7.7.1.) Supply, Delivery, and Installation	432.00	pair	76.20	32,918.40
7.8.) Grounding				
7.8.1.) Supply, Delivery, and Installation	2.00	lot	1,272.00	2,544.00
7.9.) Supply, Delivery, and Installation of Lightning Protection	2.00	lot	87,000.00	174,000.00
Total for Solar Panel & Accessories				18,972,871.60