

Section VIII. Bill of Quantities

Project Identification Number:

CW – KALINGA –48- 2022

Project Name:

UPPER CHICO RIVER
IRRIGATION SYSTEM

Location:

TABUK CITY, KALINGA

ITEMS OF WORK	QUANTITY	UNIT	AMOUNT
UCRIS, PACKAGE 2			
TEMPORARY WORKS			
A. Project Billboard	1.00	Lot	5,185.04
B. Emergency Quarantine Facility	1.00	Lot	42,470.36
UCRIS-MDC, & LAT. D. (AGB)			
CANALIZATION & PROTECTION WORKS			
A. Common Excavation (Mechanized)	24,309.87	Cu.m.	2,122,980.95
B. Backfill with Compaction (Mechanized)	15,440.62	Cu.m.	4,179,775.83
C. Gravel Blanket	330.67	Cu.m.	488,680.66
D. 170 kg./ sq.cm. Class “B” Concrete	3,088.33	Cu.m	20,772,244.57
E. 2121 kg./ sq.cm Reinforced Concrete	231.07	Cu.m.	2,427,006.67
F. Reinforcing Steel Bars	15,743.15	Kgs.	1,385,869.49
G. Waste Disposal	23,959.18	Cu.m.	3,481,268.85
H. Rubble Masonry w./o Dewatering	1,144.30	Cu.m.	7,277,439.04
I. Gabion Riprap Slope Protection	5,096.00	Cu.m.	14,989,680.16
J. Road Gravelling	67.50	Cu.m.	94,616.10
K. Clearing and Grubbing	1,278.07	Sq.m.	28,871.60
CONSTRUCTION SAFETY AND HEALTH	23,245.00	Man.day	303,347.25
APPROVED BUDGET FOR THE CONTRACT			57,599,436.57