

BILL OF QUANTITIES

(Building Construction/ Rehabilitation Project)

PROJECT TITLE : REHABILITATION OF ROAD, SIDEWALK, REINFORCED CONCRETE PIPE AND BOX CULVERT AT MARCOS STREET (STA. 00+000 TO STA. 00+370) IN BARANGAY SAN BARTOLOME

LOCATION : BARANGAY SAN BARTOLOME

PROJECT NO. : OCM-CDF(ENGINEERING)-26-FLOOD-00074

DURATION : ONE HUNDRED TWENTY (120) CALENDAR DAYS

Contract Duration: 120 Calendar Days

ITEM CODE	DESCRIPTION	QUANTITY	UNIT	ESTIMATED DIRECT COST	MARK-UP IN % OCM	PROFIT	TOTAL MARK-UP %	VALUE	VAT	TOTAL INDIRECT COST	TOTAL COST	UNIT COST
OTHER GENERAL REQUIREMENTS												
PART I												
B.5	Project Billboard/Signboard	1.00	each									
B.7(1)	Occupational Safety and Health Program	4.00	month									
B.9	Mobilization	1.00	unit									
B.9	Demobilization	1.00	unit									
TOTAL OF PART I												
PART II	EARTHWORKS											
PART A	REMOVAL OF STRUCTURES											
101(3)b3	Removal of Actual Structure/ Obstruction, 0.23m thick, PCCP (Unreinforced)	2,331.00	sq.m.									
101(3)d	Removal of Actual Structure/Obstruction, 0.10m thick, Sidewalk	1,480.00	sq.m.									
101(4)c	Removal of Actual Structure/Obstruction, Curb & Gutter	740.00	l.m.									
TOTAL OF PART II.A.												
PART B	STRUCTURE EXCAVATION											
102(2)	Roadway Excavation	245.00	cu.m.									
103(1)a	Structure Excavation, Hard Rock	3,351.00	cu.m.									
901 (1)a	Lean Concrete	11.00	cu.m.									
TOTAL OF PART II.B.												