

BILL OF QUANTITIES AND UNIT COST AS AWARDED

CONTRACT NUMBER: CW-IFUGAO-39-2026
PROJECT : PATYUKEN PALO SIP
CONTRACTOR : MR-G CONSTRUCTION

DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
MAIN CANAL				
I. DIVERSION WORKS				
a. Common Structure Excavation	2.64	cu.m	437.50	1,155.00
b. Rubble Masonry	25.02	cu.m	15,150.12	379,056.00
c. 211 kg./sq.cm. Reinf. Concrete	11.44	cu.m	22,956.99	262,627.97
II. CANALIZATION WORKS				
a. Common Excavation	88.64	cu.m	347.47	30,799.74
b. 170 kg./sq.cm. Plain Concrete	30.34	cu.m	14,485.48	439,489.46
c. Grouted Riprap	24.80	cu.m	12,175.48	301,951.90
d. Procurement, Delivery & Installation of 6" SDR 17 HDPE Pipeline	59.00	cu.m l.m	1,675.85	98,875.15
e. Backfill(Embedded Pipeline)	3.28	cu.m	277.44	910.00
f. Miscellaneous Materials				
1. Strainer	2.00	pc		
III. CANAL STRUCTURES				
a. Common Structure Excavation	1.15	cu.m	334.78	385.00
b. 211 kg./sq.cm. Reinf. Concrete	0.79	cu.m	21,381.99	16,891.77
IV. TERMINAL FACILITIES				
a. Common Structure Excavation	0.28	cu.m	1,375.00	385.00
b. 211 kg./sq.cm. Reinf. Concrete	0.14	cu.m	36,083.07	5,051.63
Project Billboard	1.00	lot	6,160.00	6,160.00
Construction Safety & Health	2,113.00	mandays	14.00	29,582.00
TOTAL CONTRACT COST				1,573,320.62

APPROVED :


RONILIO M. CERVANTES
REGIONAL MANAGER A
NIA-CAR

CONFORME:


MARIBEL B. UMILA
Authorized Managing Officer
MR-G CONSTRUCTION
