



BILL OF QUANTITIES AND UNIT COST AS AWARDED

CONTRACT NUMBER: CW-MP-21-2026
PROJECT : LADLADEGAN CIS
CONTRACTOR : JAH-ZONE CONSTRUCTION

DESCRIPTION		QUANTITY	UNIT	UNIT COST	AMOUNT
I	DIVERSION WORKS				
A	Common Structure Excavation	5.45	cum.	653.64	3,562.34
B	Rubble Masonry	28.80	cum.	13,923.65	401,001.12
C	211 kg./sq.cm. Concrete	0.87	cum.	13,076.82	11,376.83
D	Reinforcing Steel Bar, Grade 40 (see plans)	48.31	kgs.	120.56	5,824.25
E	Miscellaneous Hardware				
	Fabricated Screen Filter	3.00	pc.	581.00	1,743.00
	3.0" Ø GI Sch. 40 x 6m	2.00	pc.	5,488.00	10,976.00
	12mmØ x 6m Steel Bar	11.00	pc.	617.00	6,787.00
	2"x2"x1/4" x 6m Angle Bar	2.00	pc.	2,070.00	4,140.00
	3.0" Ø GI Coupling	1.00	pc.	581.00	581.00
II	CANALIZATION WORKS				
A	Procurement, Delivery, Manual Hauling and Installation of 1.5" Ø GI SCH. 40 Pipeline	516.00	ln.m.	443.87	229,036.92
B	Procurement, Delivery, Manual Hauling and Installation of 3.0" Ø GI SCH. 40 Pipeline	799.00	ln.m.	962.60	769,117.40
C	Miscellaneous Hardware				
	3"-1.5" GI Reducer	1.00	pc.	983.00	983.00
	3" GI Tee	1.00	pc.	1,380.00	1,380.00
	3"x0.20 GI Nipple	3.00	pc.	471.00	1,413.00
	3" GI Ball Valve	2.00	pc.	8,468.00	16,936.00
	1.5" GI Coupling	71.00	pc.	314.00	22,294.00
	3" GI Coupling	132.00	pc.	581.00	76,692.00
III	CANAL STRUCTURES				
A	Common Structure Excavation	4.75	cum.	749.97	3,562.36
B	Gravel Blanket	2.38	cum.	9,159.97	21,800.73
C	211 kg./sq.cm. Concrete w/ Water Proofing Cement	19.73	cum.	20,499.41	404,453.36
D	Reinforcing Steel Bar, Grade 40 (see plans)	1,930.69	kgs.	107.99	208,495.21
E	Miscellaneous Hardware				
	Pre-Fabricated Steel Ladder	3.00	pcs	6,272.00	18,816.00
	Marble Tank Marker	3.00	pcs	6,272.00	18,816.00
	3.0" Ø 90º GI Pipe Elbow (Supply Pipe)	6.00	pcs	745.00	4,470.00
	3.0" Ø GI Ball Valve (Supply Pipe)	4.00	pcs	8,468.00	33,872.00
	1.5.0" Ø 90º GI Pipe Elbow (Supply Pipe)	3.00	pcs	361.00	1,083.00
	1.5" Ø GI Ball Valve (Supply Pipe)	2.00	pcs	1,882.00	3,764.00
	2.0" Ø G.I. Pipe 90º Elbow (Overflow Pipe)	3.00	pcs	361.00	1,083.00