

ITEM CODE	DESCRIPTION	QUANTITY	UNIT	ESTIMATED DIRECT COST	MARK-UP IN %		%	TOTAL MARK-UP		VAT	TOTAL INDIRECT COST	TOTAL COST	UNIT COST
OTHER GENERAL REQUIREMENTS					OCM	PROFIT		VALUE					
PART I													
B.5	Project Billboard/Signboard	1.00	each										
B.7(1)	Occupational Safety and Health Program	2.00	month										
B.9	Mobilization	1.00	unit										
B.9	Demobilization	1.00	unit										
	TOTAL OF PART I												
PART II	EARTHWORKS												
PART A	REMOVAL OF STRUCTURES												
101(3)b3	Removal of Actual Structure/ Obstruction, 0.23m thick, PCCP (Unreinforced)	30.00	sq.m.										
101(3)d	Removal of Actual Structure/Obstruction, 0.10m thick, Sidewalk	30.00	sq.m.										
101(4)c	Removal of Actual Structure/Obstruction, Curb & Gutter	5.00	l.m.										
	TOTAL OF PART II.A.												
PART B	STRUCTURE EXCAVATION												
102(2)	Roadway Excavation	4.00	cu.m.										
103(1)a	Structure Excavation, Hard Rock	654.00	cu.m.										
804(4)	Gravel Fill	4.00	cu.m.										
	TOTAL OF PART II.B.												
	TOTAL OF PART II												
PART III	CIVIL WORKS												
PART A	SUB-BASE AND BASE COURSE												
200(1)	Aggregate Subbase Course	64.00	cu.m.										
201(1)	Aggregate Base Course	46.00	cu.m.										
	TOTAL OF PART III.A.												
PART B	SURFACE COURSES												
311(1)c2	Portland Cement Concrete Pavement, 0.23m thick, 7 days	357.00	sq.m.										
	TOTAL OF PART III.B.												
PART C	DRAINAGE AND SLOPE PROTECTION STRUCTURES												
500(1)a3	Pipe Culverts, 910mm dia., RPCP	129.00	l.m.										
500(5)	Tapping Drainage	14.00	set										