

BILL OF QUANTITIES AND UNIT COST AS AWARDED

CONTRACT NUMBER: CW-ALSPIP-02-2024
PROJECT : ALFONSO LISTA SOLAR PUMP IRRIGATION PROJECT 02
CONTRACTOR : JC SOLIDARITY CONSTRUCTION

DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
Construction of 6 Units 15HP Powered Pump - Well Drilled w/ AI Monitoring & Fertigation System and Lightning Protection				
1. Temporary Works, Const. Plant, Mobilization of Construction Equipment & Demobilization Works				
1.1 Mobilization & Demobilization of Equipment and Const'n Works	1.00	l.s.	648,700.80	648,700.80
1.2 Temporary Facilities	2.00	l.s.	96,000.00	192,000.00
2. Geo Resistivity	6.00	lot	102,375.00	614,250.00
3. Well Drilling	600.00	ln.m.	25,430.40	15,258,240.00
4. Well Casing and Development				
4.1.Well Development	6.00	unit	191,352.00	1,148,112.00
4.2.Gravel Pack/Gravel Filter	9.73	cu.m.	5,295.00	51,520.35
4.3.Supply and Delivery of 8" dia. uPVC Pipe x 6m	600.00	ln.m.	4,854.00	2,912,400.00
4.4. Installation of 8" dia. uPVC Pipe x 6m.	600.00	ln.m.	5,607.58	3,364,548.00
5. Pump Test	6.00	unit	47,904.00	287,424.00
6. Supply, Delivery, and Installation of 15Hp Submersible Pump, Discharge Pipe & It's Accessories				
6.1 Supply and Delivery of Pump & it's Accessories				
6.1.1 Submersible Pump (15Hp)	6.00	lot	1,914,000.00	11,484,000.00
6.1.2 Flow Meter	6.00	assy.	115,200.00	691,200.00
6.1.3 4" Hydraulic Control Valve	6.00	assy.	60,000.00	360,000.00
6.1.4 Pipes and Fittings	6.00	lot	282,000.00	1,692,000.00
6.2 Installation of Submersible Pump & it's Accessories	6.00	lot	144,864.00	869,184.00
7. Solar Panel				
7.1 Supply and Delivery of Solar Panels				
7.1.1 PV Modules (Solar Panel 600watts)	192.00	pcs	39,300.00	7,545,600.00
7.1.2 MC4 Connector	360.00	paid	1,182.00	425,520.00
7.1.3 DC Cable from PV String (1x4mm ²)	1,128.00	ln.m.	117.60	132,652.80
7.1.4 AC Cable (8.0 mm ²)	1,128.00	ln.m.	144.00	162,432.00
7.1.5 2" ø RSC Conduit	1,128.00	ln.m.	942.00	1,062,576.00
7.1.6 Grounding	6.00	lot	16,416.00	98,496.00
7.2 Installation				
7.2.1 Installation of PV Modules, Conduits, Cables and it's Accessories	6.00	unit	55,200.00	331,200.00
7.3 Supply, Delivery & Installation of Lightning Protection	6.00	lot	87,000.00	522,000.00
8 Inverter & Control Panel				
8.1 Supply and Delivery of Control Panels	6.00	lot	743,700.00	4,462,200.00
8.2 Installation of Control Panels	6.00	lot	7,920.00	47,520.00
9 Mounting Structures (Hot Dip Galvanized)				
9.1 Supply, Delivery and Fabrication	6.00	lot	1,851,000.00	11,106,000.00
9.2 Installation	6.00	lot	756,000.00	4,536,000.00
9.3 Structure Excavation (Manual)	110.52	cu.m.	1,741.93	192,518.10
9.4 Structure Backfill (Manual)	95.04	cu.m.	203.77	19,366.30
9.5 211 kg./sq.cm Concrete (Class "A") - 3000 Psi	15.54	cu.m.	21,846.66	339,497.10
9.6 Reinforcing Steel Bar, RSB (All sizes)	273.00	kgs	293.64	80,163.72
9.7 Gravel Blanket	1.30	cu.m.	6,803.15	8,844.10
10 Distribution Pipes				
10.1 HDPE ISO 4427 SDR 17 2" Ø x 6m (PE80)				
10.1.1 Supply & Delivery	240.00	pcs	2,808.00	673,920.00
10.1.2 Installation	240.00	pcs	2,820.00	676,800.00
10.1.3 Pipe Fittings	6.00	lot	21,420.00	128,520.00
11 Construction of Perimeter Fence, Stilling Pool				
11.1 Structure Excavation (Manual)	112.20	cu.m.	1,741.93	195,444.55
11.2 Structure Backfill (Manual)	97.68	cu.m.	203.77	19,904.25
11.3 Structure Excavation (Mechanized)	618.75	cu.m.	168.89	104,500.69
11.4 Gravel Blanket	112.50	cu.m.	6,803.15	765,354.38
11.5 211 kg./sq.cm Concrete (Class "A") - 3000 Psi	28.85	cu.m.	21,846.66	630,276.14
11.6 Reinforcing Steel Bar, RSB (All sizes)	3,099.90	kgs	293.64	910,254.64