



BILL OF QUANTITIES AND UNIT COST AS AWARDED

CONTRACT NUMBER: CW-MP-19-2025
PROJECT : CADAD-ANAN CIS
CONTRACTOR : LIOR-MHEI CONSTRUCTION SERVICES

DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
I. CANALIZATION WORKS				
A. Clearing and Grubbing	444.00	Sq.m	24.30	10,789.20
B. Common Excavation	33.33	Cu.m	308.20	10,272.31
C. Procurement and Delivery of 6.0" Ø HDPE Pipe SDR 17	360.00	Ln.m	1,540.80	554,688.00
D. Procurement and Delivery of 8.0" Ø HDPE Pipe SDR 17	60.00	Ln.m	3,210.00	192,600.00
E. Installation of 6.0" Ø HDPE Pipe SDR 17	360.00	Ln.m	111.10	39,996.00
F. Installation of 8.0" Ø HDPE Pipe SDR 17	60.00	Ln.m	142.80	8,568.00
G. Demolition of Concrete	2.75	Cu.m	2,077.70	5,713.68
H. Rubble Masonry	49.13	Cu.m	26,165.70	1,285,520.84
I. Manual Backfill & Compaction	18.36	Cu.m	559.50	10,272.42
J. Miscellaneous Materials & Accessories	1.00	Lot	12,004.00	12,004.00
Filter (6" Pipe)	2.00	Pcs		
Filter (4" Pipe)	1.00	Pc		
Filter (8" Pipe)	3.00	Pcs		
16mm (RM Canal Trash Rack)	13.02	Kgs		
II. CANAL STRUCTURES				
A. Common Structure Excavation	6.05	Cu.m	305.60	1,848.88
B. Procurement and Delivery of 4.0" Ø HDPE Pipe SDR 17	114.00	Ln.m	770.40	87,825.60
C. Procurement and Delivery of 8.0" Ø HDPE Pipe SDR 17	30.00	Ln.m	3,210.00	96,300.00
D. Installation of 4.0" Ø HDPE Pipe SDR 17	114.00	Ln.m	100.20	11,422.80
E. Installation of 8.0" Ø HDPE Pipe SDR 17	30.00	Ln.m	114.30	3,429.00
F. Gravel Blanket	0.20	Cu.m	15,600.60	3,120.12
G. Demolition of Concrete	2.25	Cu.m	6,933.60	15,600.60
H. Rubble Masonry	0.11	Cu.m	22,995.30	2,529.48
I. 211 kg./sq.cm Concrete	6.89	Cu.m	31,563.30	217,471.14
J. Reinforcing Steel Bars	671.83	Kgs	122.00	81,963.26
K. Manual Backfill & Compaction	2.00	Cu.m	513.60	1,027.20
L. Procurement, Delivery & Installation of 3/8" Ø Cable Wire, 6/19 IWRC	122.00	Ln.m	392.80	47,921.60
M. Other Materials & Accessories	1.00	Lot	19,160.00	19,160.00
3/8" Ø Cable Clip (Drop Forged)	10.00	Pcs		
2.0" Ø x 0.15m G.I. Cable Guide	8.00	Pcs		
16 mm Ø RSB (U-Shape & Anchor Bar)	35.80	Kgs		
# 10 Tie Wire (Suspender- 35kgs/roll)	4.00	Roll		
III. TEMPORARY WORKS				
A. Project Billboard	1.00	Lot	8,602.79	8,602.79
B. Construction Safety & Health	802.00	man-days	32.00	25,664.00
TOTAL CONTRACT COST				2,754,310.92

APPROVED :


BENITO T. ESPIQUE JR.
REGIONAL MANAGER A
NIA-CAR

CONFORME:


SHARMAN R. DUGAO
GENERAL MANAGER
LIOR-MHEI CONSTRUCTION SERVICES