

BILL OF QUANTITIES AND UNIT COST AS AWARDED

CONTRACT NUMBER: CW-APAYAO-13-2024
PROJECT : APAYAO SOLAR PUMP IP-3
CONTRACTOR : ASC CONSTRUCTION & CONCRETE PRODUCTS

DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
LOT 1 (MALUBIBIT SUR, FLORA, APAYAO)				
A. MOBILIZATION AND DEMOBILIZATION & PROJECT BILLBOARD				
A.1. Mobilization and Demobilization	1.00	lot	527,479.92	527,479.92
A.2. Project Billboard	1.00	lot	8,529.99	8,529.99
B. CONSTRUCTION SAFETY AND HEALTH PROGRAM				
B.1. Construction Safety and Health Program	1.00	ls	206,413.02	206,413.02
C. SUPPLY, DELIVERY, AND INSTALLATION OF 15 HP SURFACE PUMP, DISCHARGE PIPE & ACCESSORIES				
C1. Supply, Delivery, and Installation				
C.1.a. Surface Pump (15hp)	3.00	lot	1,866,051.00	5,598,153.00
C.1.b. Flow Meter	3.00	assy	111,117.60	333,352.80
C.1.c. 4" Hydraulic Control Valve	3.00	assy	60,390.00	181,170.00
C.1.d. 4" Pipe and Fittings	3.00	units	200,494.80	601,484.40
C.2. Installation of Surface Pump, Flow Meter, Hydraulic Control Valve, and Pipes with Fittings	3.00	units	215,954.64	647,863.92
D. SOLAR PANEL				
D.1. Supply and Delivery				
D.1.a. PV Modules (Solar Panel 700 watts)	96.00	pcs	48,312.00	4,637,952.00
D.1.b. MC4 Connector	216.00	pairs	966.24	208,707.84
D.1.c. DC Cable from PV String (1x4mm ²)	672.00	ln.m	157.01	105,510.72
D.1.d. AC Cable (8.0 mm ²)	672.00	ln.m	217.40	146,092.80
D.1.e. 2" Ø RSC Conduit	672.00	ln.m	1,026.63	689,895.36
D.1.f. Grounding	3.00	lot	50,727.60	152,182.80
D.2. Installation of PV Modules, Conduits, Cables and Accessories	3.00	unit	150,371.10	451,113.30
E. INVERTER AND CONTROL PANEL				
E.1. Supply & Delivery	3.00	unit	724,680.00	2,174,040.00
E.2. Installation	3.00	unit	16,305.30	48,915.90
F. MOUNTING STRUCTURE				
F.1. Mounting Structures (Hot Dip Galvanized)				
F.1.a. Supply, Delivery and Fabrication	3.00	units	1,992,870.00	5,978,610.00
F.1.b. Installation	3.00	units	881,100.00	2,643,300.00
F.2. Structure Excavation (Manual)	13.05	cu.m	322.09	4,203.27
F.3. Structure Backfill (Manual)	7.65	cu.m	339.70	2,598.71
F.4. Class A Concrete	4.32	cu.m	24,617.26	106,346.56
F.5. Reinforcing Steel Bar				
F.5.a. Furnishing and Stockpiling	1,001.68	kgs	108.70	108,882.62
F.5.b. Cut, Bend, and Place	1,001.68	kgs	33.98	34,037.09
F.6. Gravel Blanket	69.05	cu.m	6,197.88	427,963.61
F.7. Painting Works	13.50	sq.m	495.20	6,685.20
G. CONSTRUCTION OF PERIMETER FENCE, STILLING POOL AND NIA LOGO				
G.1. Structure Excavation (Manual)	32.71	cu.m	362.34	11,852.14
G.2. Structure Backfill (Manual)	6.77	cu.m	392.54	2,657.50
G.3. Class A Concrete, 211 kg/sq.cm	36.01	cu.m	24,617.26	886,467.53
G.4. Reinforcing Steel Bar				
G.4.a. Furnishing and Stockpile	2,340.65	kgs	108.70	254,428.66
G.4.b. Cut, Bend and Install	2,340.65	kgs	36.49	85,410.32
G.5. 4" thk. CHB (Laying & Plastering of Both Sides)				
G.5.a. Laying	69.66	sq.m	1,825.86	127,189.41
G.5.b. Plastering	139.32	sq.m	420.86	58,634.22
G.6. Cyclone Chain Wire	243.00	ln.m	722.26	175,509.18
G.7. 2" Ø G.I Pipe(sch. 40)	420.60	ln.m	1,002.47	421,638.88
G.8. Painting Works	123.68	sq.m	495.20	61,246.34
G.9. Water Proofing	25.65	sq.m	1,582.22	40,583.94
G.10. Gravel Blanket	8.02	cu.m	6,197.88	49,707.00
G.11. Red Oxide Metal Primer	245.10	sq.m	857.54	210,183.05
G.12. Solar Street Light	15.00	pcs	71,260.20	1,068,903.00
H. DISTRIBUTION PIPES				
H.1. HDPE ISO4427 SDR 17 4" DIA X 6M (PE 80)				
H.1.a. Supply & Delivery	606.00	pcs	6,449.65	3,908,487.90
H.1.b. Installation	606.00	pcs	2,343.13	1,419,936.78
H.2. Pipe Fittings	3.00	lot	422,730.00	1,268,190.00
H.3. 4" LAYFLAT PIPE (Including end connectors)				
H.3.a. Supply & Delivery	18.00	roll	22,948.20	413,067.60
H.3.b. Installation	18.00	roll	543.51	9,783.18
H.4. 3" LAYFLAT PIPE (Including end connectors)				
H.3.a. Supply & Delivery	9.00	roll	18,117.00	163,053.00
H.3.b. Installation	9.00	roll	434.81	3,913.29
H.5. 2" LAYFLAT PIPE (Including end connectors)				
H.5.a. Supply & Delivery	9.00	roll	14,493.60	130,442.40
H.5.b. Installation	9.00	roll	326.11	2,934.99