

PROJECT TITLE : REHABILITATION OF PAYATAS A HEALTH CENTER WITH INSTALLATION OF SOLAR POWER SYSTEM INCLUDING BATTERY STORAGE
LOCATION : BARANAGAY PAYATAS
PROJECT NO. : ENGINEERING-26-BLDG-00100
DURATION : 150 CALENDAR DAYS

ITEM CODE	DESCRIPTION	QUANTITY	UNIT	ESTIMATED DIRECT COST	MARK-UP IN %		TOTAL MARK-UP		VAT	TOTAL INDIRECT COST	TOTAL COST	UNIT COST
					OCM	PROFIT	%	VALUE				
1101	Outlet with Grounding, One-Gang	7.00	piece									
1101	Outlet with Grounding with TRR, Two-Gang	31.00	piece									
1101	Outlet with Grounding, One-gang, for ACU, Heavy Duty	6.00	piece									
1101	Two Gang Universal GFCI Outlet with plate	5.00	piece									
1101	Emergency Light, Dual Optics	5.00	piece									
1101	LED Exit Light, 3W, 360mmx150mmx25mm	2.00	piece									
F.3. Panelboard with Main and Branch Breakers												
1102	Main Enclosed Circuit Breaker (MECB), 125AT, 200AF, 2P, NEMA 4X with Ground Terminals and Digital Monitoring Display	1.00	assy									
1102	Lighting and Power Panel, 125AT, 200AF, 2P, Branches: 1-70AT, 2P, 8-20AT,2P , 9-30AT, 2P in NEMA 1 with Ground Terminals and Digital Monitoring Display	1.00	assy									
1102	Manual Transfer Switch with Enclosure, 30AT, 2P, Complete Set with 20mmØ PVC Locknut and Bushing	1.00	assy									
F.4. Lighting Fixtures and Lamps												
1103(1)	2x18W LED Tube, Recessed Mounted Troffer Type, Complete accessories, (600mm x 1200mm)	16.00	set									
1103(1)	600mm x 600mm,Recessed Mounted Panel Light 40W	4.00	set									
1103(1)	Recessed Downlight, 6 inch, Plain Mirrorized Aluminum Refelctor with 9Watts Daylight LED	2.00	set									
1103(1)	1 x LED Tube light, Box type with 18W Daylight LED Tube	4.00	set									