

BILL OF QUANTITIES AND UNIT COST AS AWARDED

CONTRACT NUMBER: CW-APAYAO-13-2024
PROJECT : UCRIS - TIWONG SOLAR PUMP IRRIGATION PROJECT (SPIP) PHASE2
CONTRACTOR : ASC CONSTRUCTION & CONCRETE PRODUCTS

DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
LOT 1 UPPER CHICO RIVER IRRIGATION SYSTEM SPIP				
CONSTRUCTION OF (5) UNIT 15HP SOLAR PV SUBMERSIBLE PUMPING SYSTEM- OPEN SOURCE				
1. Mobilization and Demobilization & Facilities				
1.a. Mobilization and Demobilization	1.00	lot	1,940,859.04	1,940,859.04
1.b. Construction of Worker Shed/Bodega (7 x 5 meters)	2.00	lot	118,800.00	237,600.00
1.c. Project Billboard @ 1 unit/lot	1.00	lot	14,874.31	14,874.31
2.SUPPLY, DELIVERY AND INSTALLATION OF 15 HP SUBMERSIBLE PUMP, DISCHARGE PIPE & ACCESSORIE			-	-
2.1 Supply, Delivery & Installation				
2.1.a. Submersible Pump(15hp)	5.00	lot	1,975,659.84	9,878,299.20
2.1.b. Flow Meter	5.00	assy	111,474.32	557,371.60
2.1.c. 4" Check Valve	5.00	assy	63,456.62	317,283.10
2.1.d. Pipe and Fittings	5.00	units	189,565.22	947,826.10
2.2 Installation of Submersible Pump,Flow Meter, Hydraulic Control Valve and Pipes with Fittings	5.00	units	191,589.94	957,949.70
3. SOLAR PANEL				
3.1. Supply and Delivery				
3.1.a. PV Modules (Solar Panel 600watts)	300.00	pcs	38,832.84	11,649,852.00
3.1.b. MC4 Connector	675.00	pairs	868.76	586,413.00
3.1.c. DC Cable from PV String (1x4mm ²)	2,100.00	ln.m	143.93	302,253.00
3.1.d. AC Cable (8.0 mm ²)	2,100.00	ln.m	147.85	310,485.00
3.1.e. 2" Ø RSC Conduit	2,100.00	ln.m	882.72	1,853,712.00
3.1.f. Grounding	5.00	lot	14,516.52	72,582.60
3.2. Installation				
3.2.a. Installation of PV Modules, Conduits, Cables and Accessories	5.00	unit	108,805.22	544,026.10
4. INVERTER & CONTROL PANEL				
4.a. Supply & Delivery	5.00	units	729,424.08	3,647,120.40
4.b. Installation	5.00	units	14,479.89	72,399.45
5. MOUNTING STRUCTURE (HOT DIP GALVANIZED)				
5.1.a. Supply, Delivery and Fabrication	5.00	units	1,822,508.26	9,112,541.30
5.1.b. Installation	5.00	units	765,453.47	3,827,267.35
5.2. Structure Excavation (Manual)	21.60	cu.m	380.44	8,217.50
5.3. Backfill (Manual)	12.15	cu.m	409.85	4,979.68
5.4. 211 kg./sq.cm Concrete (Class "A")	10.80	cu.m	27,066.42	292,317.34
5.5. Gravel Blanket	115.10	cu.m	4,623.50	532,164.85
5.6 Reinforcing Steel Bar	1,669.78	kgs.	127.70	213,230.91
5.7 Painting Works	22.50	sq.m	485.08	10,914.30
6. CONSTRUCTION OF PERIMETER FENCE, STILLING POOL AND NIA LOGO				
6.1. Structure Excavation (Manual)	68.43	cu.m	380.44	26,033.51
6. 2. Backfill (Manual)	30.83	cu.m	409.85	12,635.68
6.3. 211 kg./sq.cm Concrete (Class "A")	31.38	cu.m	27,160.59	852,299.31
6.4. Reinforcing Steel Bar	2,508.04	kgs.	127.70	320,276.71
6.5. 4" thk. CHB (Laying & Plastering of Both Sides)	171.41	sq.m	2,704.85	463,638.34
6.6. Cyclone Chain Wire	515.25	ln.m.	756.16	389,611.44
6.7. 2" Ø G.I Pipe (sch. 40)	876.00	ln.m.	1,351.97	1,184,325.72
6.8. Painting Works	53.43	sq.m	485.08	25,917.82
6.9. Water Proofing	100.00	sq.m	1,660.67	166,067.00
6.10. Gravel Blanket	17.85	cu.m	4,623.50	82,529.48
6. 11. Red Oxide Metal Primer	140.00	sq.m	1,566.14	219,259.60
6. 12. Solar Street Light	12.00	pcs	10,313.33	123,759.96
7.CONSTRUCTION OF CONTROL HOUSE				
7.1. Structure Excavation (Manual)	16.09	cu.m	380.44	6,121.28
7. 2. Backfill (Manual)	7.02	cu.m	409.85	2,877.15
7.3. 211 kg./sq.cm Concrete (Class "A")	21.64	cu.m	27,160.59	587,755.17
7.4. Reinforcing Steel Bar	2,071.23	kgs.	127.70	264,496.07
7.5. 4" thk. CHB (Laying & Plastering of Both Sides)	127.41	sq.m	2,704.85	344,624.94
7.8. Painting Works	358.45	sq.m	485.08	173,876.93
7.9. Water Proofing	61.25	sq.m	1,598.85	97,929.56
7.10. Gravel Blanket	5.36	cu.m	4,623.50	24,781.96
8.INTAKE WORKS				
8.1 Concrete Demolition	11.33	cu.m	1,236.42	14,008.64
8.2 Common Structure Excavation (Mechanized)	2,667.99	cu.m	384.66	1,026,269.03
8.3 Gravel Blanket	5.72	cu.m	4,623.50	26,446.42
8.4 Supply and Delivery of 20" Ø HDPE Pipes SDR 17	250.00	ln.m	15,046.42	3,761,605.00
8.5 Installation of 20"Ø HDPE Pipes SDR 17	250.00	ln.m	1,301.04	325,260.00