

BILL OF QUANTITIES AND UNIT COST AS AWARDED

CONTRACT NUMBER: CW-BENGUET-01-2025
PROJECT : TULUDAN CIS
CONTRACTOR : BOTJACK CONSTRUCTION

DESCRIPTION	QUANTITY	UNIT	UNIT COST	AMOUNT
I. TEMPORARY WORKS				
Project Billboard	1	lot	5,087.89	5,087.89
II. CONSTRUCTION SAFETY AND HEALTH PROGRAM				
Personal Protective Equipment (PPE)	3,436.00	man-days	18.45	63,394.20
III. CANALIZATION WORKS				
Clearing and Grubbing	10,560.00	sq.m.	25.55	269,808.00
Proc/Delivery/Hauling/Inst'n of 1.0"Ø HDPE Pipe, SDR 13.5 (Black)	7,980.00	ln.m	86.10	687,078.00
Proc/Delivery/Hauling/Inst'n of 1.0"Ø GI Pipe, Sch. 40	820.00	ln.m.	369.16	302,711.20
IV. TERMINAL FACILITIES				
Clearing and Grubbing	131.30	sq.m.	24.46	3,211.60
Common Structure Excavation	87.20	cu.m	380.45	33,175.24
Gravel Blanket	3.91	cu.m	16,499.40	64,512.65
211 kg/sq.cm Reinforced Concrete	27.96	cu.m	43,523.73	1,216,923.49
V. PUMPING				
Common Structure Excavation	13.44	cu.m	366.85	4,930.46
Gravel Blanket	0.68	cu.m	16,499.40	11,219.59
211 kg/sq.cm Reinforced Concrete	2.98	cu.m	43,239.87	128,854.81
Laying and Plastering of Concrete Hollow Blocks	24.70	sq.m.	4,521.68	111,685.50
Proc/Delivery/Inst'n of Wooden Structures/Members	244.00	bd.ft	402.13	98,119.72
Proc/Delivery/Inst'n of Pre-painted Rib Type GI Sheets and Other Finishings/	19.52	sq.m.	1,770.70	34,564.06
Proc/Delivery/Inst'n of Steel Door	2.00	set	14,061.53	28,123.06
Proc/Delivery/Inst'n of Steel Casement Windows	4.00	set	14,061.53	56,246.12
Proc/Delivery/Inst'n of Piston Type Pump w/ 18 HP Diesel Engine and Compl	2.00	set	257,660.28	515,320.56
VI. MISCELLANEOUS MATERIALS AND ACCESSORIES				
ALONG PIPELINE				
1"Ø x 1/2"Ø Saddle Clamp	5.00	pcs	542.60	2,713.00
1/2"Ø GI Nipple x 4"	10.00	pcs	77.07	770.70
1/2"Ø GI Ball Valves	5.00	pcs	1,078.97	5,394.85
3/8"Ø Cable Wire (6 x 19 S WRC - Steel Core)	440.00	ln.m.	191.06	84,066.40
3/8"Ø Cable Clip	20.00	pcs	172.68	3,453.60
1"Ø GI Coupling	101.00	pcs	231.41	23,372.41
1"Ø GI Check Valve	9.00	pcs	2,024.44	18,219.96
1"Ø GI Union	26.00	pcs	597.29	15,529.54
#12 Tie Wire (35kgs/roll)	6.00	rolls	7,107.17	42,643.02
#6 Tie Wire (35kgs/roll)	6.00	rolls	7,107.22	42,643.32
RESERVOIR TANK				
2"Ø Pre-fab Distribution Pipe - 8 outlets (Welded Part)	5.00	pcs	11,101.25	55,506.25
2"Ø Pre-fab Outlet Pipe - 2 outlets (Welded Part)	1.00	pcs	5,998.35	5,998.35
1"Ø x 1"Ø Compression Coupler	2.00	pcs	595.05	1,190.10
2"Ø GI Drain & Overflow Nipple x 12"	10.00	pcs	597.29	5,972.90
2"Ø GI Ball Valves	5.00	pcs	4,243.95	21,219.75
1"Ø GI Ball Valves	2.00	pcs	1,637.73	3,275.46
2"Ø GI 90° Elbow	5.00	pcs	559.84	2,799.20
1.75M - 2"Ø GI Pipe Sch. 40	5.00	pcs	760.78	3,803.90
1/2"Ø GI Ball Valves	40.00	pcs	1,080.27	43,210.80
1/2"Ø GI Nipple x 6"	40.00	pcs	116.32	4,652.80
Tank Marker (Bronze plate marker)	5.00	pcs	8,189.99	40,949.95
Pre-fabricated Steel Ladder (D16mm)	5.00	pcs	5,823.63	29,118.15
3/4"Ø HDPE Distribution Pipe	900.00	ln.m.	51.08	45,972.00
INTAKE TANK				
2"Ø GI Drain & Overflow Nipple x 12"	4.00	pcs	596.53	2,386.12
2"Ø GI Ball Valves	2.00	pcs	4,238.80	8,477.60
2"Ø GI 90° Elbow	2.00	pcs	560.45	1,120.90
TOTAL CONTRACT COST				4,149,427.18

APPROVED :


BENITO T. ESPIQUE, JR.
REGIONAL MANAGER A
NIA-CAR

CONFORME:


JICK A. MARIANO
GENERAL MANAGER
BOTJACK CONSTRUCTION